

From: Nathan Nathan@vallettasurfacing.co.uk 
Subject: Footpath
Date: 14 January 2022 at 12:50
To: Frank Ball Frank.Ball@lynehamandbradenstoke-pc.gov.uk
Cc: Parish Clerk Parish.Clerk@lynehamandbradenstoke-pc.gov.uk



Hi Frank,

The first section of path we looked at was 320m long. Working on 1.5m path, excavated and spoil tipped on site, and then 225mm of type 1 and 60mm of nondeer course and 20mm of surface course laid inside concrete edgings. Then 200m of pig mesh fencing and timber posts. This come to just under £60k plus vat.

The second section of footpath is 330m long. Its going to need full road kerbs against the road and traffic lights so is going to be similar money, if not a bit more as the spoil may have to be taken away?

Let me know if you want me to put these in a quote, they came to quite a bit so not sure if that's way over your budget or not?

Ive allowed for 305mm construction (225mm of type 1 and 80mm of surfacing) as this is Wiltshire's footpath spec as I assume they will possibly adopt this? If they aren't that spec could be reduced a bit. They would possibly want street lighting though to adopt?

Regards

Nathan Browne



Valletta Surfacing Ltd
Five Lords Farm
Standerwick
Clivey
BA11 2RR

Tel 01373 823827
Mob 07713788860
www.vallettasurfacing.co.uk